

Central Rivers Train Maintenance Depot.

1,097 m2

SignaGrip

This railway underwent a significant transformation. The original coating system was failing due to contamination from oil within the substrate, leading to widespread delamination. Our team removed the defective coating, thoroughly prepared the substrate & walls and applied an oil-tolerant primer to ensure proper adhesion.

To rebuild the surface, we applied a scratch coat followed by two layers of high-build epoxy. Natural quartz was incorporated to enhance slip resistance, and the project was completed with clearly defined safety demarcations for improved visibility and safety.



